

**ADDENDUM NO. 2**

**RAWHIDE CREEK BASIN DRAINAGE AND ADA IMPROVEMENTS**

**TOWN OF ADDISON, TEXAS  
PUBLIC WORKS AND ENGINEERING SERVICES  
BID NUMBER 22-75**

**08/27/2022**



TO: All Plan Holders of Record

This Addendum forms part of the Contract Documents and modifies the Contract Documents and Specifications, as noted below. Acknowledge receipt of the Addendum in the space provided on the Proposal Form and on the outer envelope of the Proposal. Failure to acknowledge receipt of this Addendum may subject the Bidder to disqualification.

This Addendum consists of 2-pages and no attachments.

**QUESTIONS RECEIVED ON CIVCAST PRIOR TO DEADLINE FOR QUESTIONS ON WEDNESDAY, AUGUST 24, 2022 AT 05:00 PM CST**

Q1. Can you please provide an engineer's estimate on this project. Thank you

**Answer: N/A**

Q2. Where will the bid results be posted for those of us unable to attend the bid opening?

**Answer: Yes**

**Answer: Yes they will be uploaded to Civcast**

Q3. Hello, line B starting at 12+48.35. Profile notes indicates 22 LF of 30" RCP but plan view shows 24" all the way to the curb inlet. Can you please clarify? Thank you

**Answer: Should be 24" RCP not 30". See Addendum No. 1.**

Q4. Hope I didn't miss a note but what is the purpose of including sheet 45 in the plan set? Will our project affect their primary access? Thank you

**Answer: No, this project will not affect their primary access.**

Q5. Bid item 49: Element Bollards will require electrical wiring. Do we know where or how far the nearest power source is? Is there an existing pedestal? Will one be required? Just trying to find what we are needing to carry to include power source. Thank you.

**Answer: There is a Jbox that connects power to the existing bollards and the nearby electrical panel located south near the junction of the trails.**

Q6. Bid item 53 Trail signage indicates TBD. City website refers to plans and so do the specifications. Can you provide more details on this? If not, will there be an allowance amount you need bidder to carry? Thanks

**Answer: An allowance for \$3500 will be used for this item. See Addendum No. 1.**

Q7. Bid Item 52, sku 1004 has multiple options. Please indicate how many stations are required for this bid item, thank you.

**Answer: See Sheet 54 for detailed information**

Q8. Note #4 on TCP indicate temporary paving requirement. Will the Town/Engineer allow Flexbase (TXDOT Item 247) as a suitable temporary driving surface until actual paving can be installed?

**Answer: Yes, but no longer than 10 business days unless otherwise approved by the Engineer and must be maintained to ensure a drivable surface.**

Q9. Assuming the lane closure on tcp on Marsh lane is for delivery of Stormtrap and related equipment, will city allow removal/trimming of trees/canopy that are NOT shown on demo plan to allow access?

**Answer: City will work with contractor to determine a path to move in the equipment and tree trimming by an arborist would be allowed. Removal of a few hackberry trees could be approved if there was no other way to get equipment to the site.**

**END OF ADDENDUM NO. 2**